



LEGEND	
EXISTING	
	SOIL BORING
	PIPELINE
	NAVIGATION CHANNEL
	RIVER MILE
PROPOSED	
	BORROW BOTTOM OF CUT
	DREDGE CUT EXTENT
	TOP OF CUT
	ANCHOR BUOY LINE
	DREDGE PIPELINE CORRIDOR

NOTE:
DESIGNATED SINGLE PIPELINE CROSSING
MUST OCCUR BETWEEN THE NORTHERN
AND SOUTHERN LIMITS OF THE BORROW AREA

CONTRACTOR SHALL UTILIZE BBBB DREDGE
PIPELINE CONVEYANCE CORRIDOR AFTER CROSSING
FEDERAL NAVIGATION CHANNEL

150' DREDGE PIPELINE CORRIDOR
(SEE SHEET 56)

**Order of work will begin with the
southern half of the borrow area
excavating in a southern direction
from the east bank towards the
navigation channel.**

DDDD EXTENTS			
PT.	EASTING	NORTHING	E.L. (ft.)
1	3,926,662	276,668	-60
2	3,926,589	276,747	-60
3	3,926,101	277,104	-60
4	3,925,616	277,472	-60
5	3,925,204	277,810	-60
6	3,924,195	278,641	-60
7	3,924,208	278,694	-65
8	3,923,637	279,129	-65
9	3,922,643	279,928	-65
10	3,921,113	281,175	-65
11	3,919,543	282,463	-65
12	3,917,640	283,934	-65
13	3,916,394	284,999	-65
14	3,916,846	285,459	-65
15	3,917,392	286,014	-65
16	3,918,695	284,829	-65
17	3,920,175	283,486	-65
18	3,921,667	282,153	-65
19	3,922,970	280,988	-65
20	3,924,766	279,355	-65
21	3,924,804	279,362	-60
22	3,925,401	278,849	-60
23	3,926,864	277,430	-60
24	3,926,759	277,107	-60

DDDD BORROW AREA
TOTAL VOLUME = 17,035,500 C.Y.

SOIL BOREHOLE TABLE		
NUMBER	EASTING	NORTHING
VA-6	3,917,091	285,437
VA-8	3,918,284	284,036
VA-10	3,920,698	282,108
VA-12	3,922,573	280,979
VA-14	3,924,559	279,068

DDDD BORROW AREA EXTENT
AT BOTTOM OF CUT (-60' NAVD 88)
SEE TABLES FOR COORDINATES

Baird.
Innovation Engineered

**COASTAL PROTECTION
AND RESTORATION
AUTHORITY**
150 TERRACE AVENUE
BATON ROUGE, LOUISIANA 70802

DDDD BORROW AREA
LAYOUT

DESIGNED BY: B.H.P.E.
APPROVED BY: GGT.P.E.

STATE PROJECT NUMBER: BA-0203
DRAWN BY: BKC

DATE: 10/05/2020
SHEET 49 OF 65